

PRV

PATENT- OCH REGISTRERINGSVERKET
Patentavdelningen

5604/1487

REC'D 28 OCT 2004

WIPO

PCT

Intyg Certificate

Härmed intygas att bifogade kopior överensstämmer med de handlingar som ursprungligen ingivits till Patent- och registreringsverket i nedannämnda ansökan.

This is to certify that the annexed is a true copy of the documents as originally filed with the Patent- and Registration Office in connection with the following patent application.

- (71) Sökande Anoto AB, Lund SE
Applicant (s)
- (21) Patentansökningsnummer 0302884-2
Patent application number
- (86) Ingivningsdatum 2003-10-31
Date of filing

Stockholm, 2004-10-18

För Patent- och registreringsverket
For the Patent- and Registration Office


Gunilla Larsson

Avgift
Fee

PRIORITY DOCUMENT

SUBMITTED OR TRANSMITTED IN
COMPLIANCE WITH RULE 17.1(a) OR (b)

BEST AVAILABLE COPY

PATENT- OCH
REGISTRERINGSVERKET
SWEDEN

Postadress/Adress
Box 5055
S-102 42 STOCKHOLM

Telefon/Phone
+46 8 782 25 00
Vx 08-782 25 00

Telex
17978
PATOREG S

Telefax
+46 8 666 02 86
08-666 02 86

AWAPATENT AB

Kontor/Handläggare

Ansökningssnr

Huvudföretag Kässan
Var 2003-10-31

1

INFORMATION MANAGEMENT UNIT AND METHOD FOR CONTROLLING
DATA FLOW FROM ELECTRONIC PENS

Field of the Invention

The present invention relates to information management systems, and in particular to the distribution of electronic data from electronic pens to destination units in such systems.

Background Art

Electronic pens can be used for generation of electronic information that reflects handwritten entries on a base. Such electronic information may be generated by the electronic pen itself, the base or an external supervision device sensing the motion pattern of the pen on the base.

It would be desirable to incorporate such electronic pens in an information management system such that the electronic information could be efficiently conveyed to different destination units for further processing.

In WO 01/48685, WO 01/48678 and WO 01/48591, which are herewith incorporated by reference, the present Applicant has suggested such information management systems in which a position code is applied to each base to code a plurality of absolute positions thereon. By reading the position code, the electronic pens are capable of electronically recording a sequence of positions that reflect their own motion on the base.

The position code on each base is a subset of a much larger abstract position-coding pattern. Examples of such abstract patterns are described in WO 01/26032, WO 00/73983 and WO 99/50787. The abstract pattern may be dynamically or statically divided into subsets of given size, each such subset being associated in the system with a unique identifier. If each subset is intended for

2003-10-31

Håvard Kåresen

2

5 a respective physical page, it is denoted a logic page and is represented by a unique page address. In such a case, each absolute position may be represented by a page address and a local position within the associated logic page.

10 By dedicating different parts of the abstract pattern to different destination units, the electronic information can be automatically directed from the pen to the correct destination unit for processing. For example, the system may include an intermediary server which, upon receipt of one or more positions from a pen, identifies an associated network address of the correct actor and directs the flow of data to this address.

15 For example, an actor may provide a position-coded product which is dedicated to one or more general services, such as taking notes, sending electronic mails, sending faxes, etc. Other actors may provide a position-coded product which is dedicated to highly specialized services, such as ordering certain goods, filing time reports, filing inventory lists, etc. All such actors must develop and produce products with a unique position code, by associating parts of the position code with specific processing instructions, suitably supported by corresponding graphics on the product. The actors must also develop a service, i.e. software that communicates with the pens and selectively executes the specific processing instructions on the received data.

20 A development tool for producing such position-coded products and corresponding service software is disclosed in WO 02/19260. Further, a protocol for use in the data exchange with such electronic pens is disclosed in WO 03/005181, in which the pens are able to communicate both position data and one or more pen-resident parameters that identify characteristics of the pen or the pen user/owner in the system.

35 The complexities of developing a product, and supplying the same in sufficient quantities and with

2003 -10- 3 1

Huvudfoxen Kassen

3

adequate circulation on the market, and also of developing a service may serve as a barrier to the introduction and adoption of the electronic pen technology.

Summary of the Invention

5 It is an object of the present invention to provide
a solution to, or at least mitigate, the above-mentioned
problem.

This and other objects, which will be evident from the following description, are achieved wholly or partly by an information management unit according to claim 1, and a method according to claim 22. Preferred embodiments are defined by the dependent claims.

By including one or more pen-resident parameters in the flow control between the electronic pens and the destination units, it is possible to break up the strict one-to-one relationship between product and service. Generally speaking, electronic data from any one product can be conveyed to any one service. For one, a position-coded product can be used by several actors, i.e. position data which is recorded from one and the same product can be conveyed to different destination units depending on the actual properties of the pen that recorded the position data. This potentially reduces the need for actors to develop and distribute products that are customized to the offered services, since pre-existing products may be utilized.

30 Additionally, the efforts put into the development
of a service can be reduced, or even eliminated, by
centralized preprocessing of the electronic data from the
pens in conjunction with the flow control. To this end,
the inventive flow control can be installed in an
existing service to define one or more sub-services that
capitalize on the offerings of the existing service. For
example, an actor providing communications services, such
35 as electronic mail, via position-coded products may offer
other actors to use one or more existing communications
services for any other data collection service, provided

2003 -10- 3 1

Huvudfaxen Kassan

4

that the data collection service is intended for use by a confined group of electronic pens. By means of the inventive flow control, the communications service will be able to separate out the electronic data from the confined group of pens, and send this data, possibly after some preprocessing, via the communications service to the destination unit of the relevant actor.

The inventive flow control may be incorporated in an intermediary server, which may have an administrative interface allowing at least the operator of the intermediary server to modify or update the flow control. For example, a new flow control object may be created at will and associated with an arbitrary processing instruction. The flow control object may be created by logically combining selected values of selected control parameters, which are derivable from the electronic data transmitted by the pens. The processing instruction may define a network address of the destination unit, and optionally, a communications channel to the destination unit and/or a format of the electronic data to be conveyed to the destination unit and/or a background image to be included in the data flow to the destination unit.

Brief description of the drawings

Preferred embodiments of the invention will be described in more detail below with reference to the accompanying drawings.

Fig. 1 shows an information management unit according to one embodiment of the present invention.

Fig. 2 illustrates steps of adding a flow control object in the information management unit of Fig. 1.

Fig. 3 illustrates steps of performing flow control according to an embodiment of the invention.

Figs 4a-4c show the information management unit of Fig. 1 as incorporated in three different prior-art information management systems.

Description of preferred embodiments

The following description is based on the use of the above-identified abstract position-coding pattern, which is subdivided into page units. The page units can be part of superordinate subsets of the pattern. For example, the pattern may contain "segments" which in turn may be divided into a number of "shelves", each containing a number of "books" which may be divided into a number of aforesaid page units, also called "logic pages". The position of a certain logic page in the abstract pattern can thus be noted as a page address of the form: section.segment.shelf.book.page, for instance 1.231.841.334.226, more or less like an IP address.

The following description is also based on each product containing position code that corresponds to one or more logic pages. It is to be noted, however, that the position code on a product need not conform with a logic page. Thus, one or more subsets from one or more logic pages may be arbitrarily arranged on the product. The product may also contain functional areas that each is associated with a particular function to operate on any pen strokes therein. Each product is represented by a definition file (PAD file) which identifies the page address(es) of the relevant logic page(s), and defines the mapping of the logic page(s) on the product, the placement and size of each functional area on the logic page(s), as well as the associated function. Each product is also represented by a graphics file which defines the human-readable information on the product, i.e. the layout, which aims at instructing, controlling and/or informing a user.

A pen may record its motion on a position-coded product as a page address and a sequence of local positions on the corresponding logic page. Thus, a physical pen stroke is recorded as an electronic pen stroke in the form of a sequence of positions. The pen may then trans-

+46 40 260516

2003-10-31

Huvudfaxen Kansen

6

mit the recorded position data in the form of one or more page addresses and local positions.

As also identified by way of introduction, the electronic pens store one or more parameters, which may be transmitted in association with the position data. These pen-resident parameters either identify a characteristic of the pen itself or of the owner/user of the pen. The pen-resident parameters include: PEN_ID (a unique identifier of the pen), OPERATOR_ID (a unique identifier of the operator providing network access to the pen), PEN_OWNER_LANGUAGE, PEN_OWNER_NAME, PEN_OWNER_ADDRESS, PEN_OWNER_EMAIL, PEN_OWNER_HOME_PHONE, PEN_OWNER_CELL_PHONE, PEN_OWNER_BUSINESS_PHONE, PEN_OWNER_PAGER, PEN_OWNER_HOME_FAX, and PEN_OWNER_BUSINESS_FAX.

The electronic pens and the position-coded products are suitably combined with infrastructure components in a network-based information management system, to allow for transparent distribution of the recorded position data to adequate destination units.

One such infrastructure component is an intermediary server or flow controller 2, as shown in Fig. 1, which controls the flow of data from the pens to the destination units.

The flow controller 2 includes an input interface 4 for communication with the electronic pens, either directly or indirectly, and an output interface 6 for communication with the destination units, either directly or indirectly.

The flow controller 2 also has a processing unit 8 for controlling the flow of data from the pens to the destination units, via the input and output interfaces 4, 6, and a storage 10 which permanently stores rule objects and associated processing instructions. An administrative interface 12 is connected to the storage 10 to provide access to the rule objects and processing instructions, for example allowing an authorized operator to

+46 40 260516

Ink. t. Patent- och reg.verket

2003 -10- 3 1

Huvudfaxen Kassen

7

add/delete/edit the rule objects and/or processing instructions.

The flow controller 2 may be implemented as a network server, e.g. a web server, with communication interface hardware, controlling software, a processor (e.g. CPU, DSP, FPGA, ASIC, etc), and storage memory (e.g. RAM, ROM, PROM, EPROM, hard disk, etc).

The operation of the flow controller will now be exemplified with reference to Fig 2. In this example, the flow controller is configured to effect, in addition to flow control, one or more default services.

The processing unit 8 (Fig. 1) receives data from an electronic pen via the input interface (step 20), and extracts one or more position parameters, e.g. the page address (step 21). The value of each position parameter is matched against the rule objects to identify if flow control is to be effected (step 22). If not, the default service is accessed in conventional manner (step 23). If a match is found, the processing unit extracts values of existing pen-resident parameters in the received data (step 24). These values, optionally together with the position parameter value(s), are then mapped against the rule objects in the storage (step 25). If no match is found, the default service may be executed (step 23). If a match is found, the associated processing instruction is identified (step 27), whereupon flow control is executed based thereon (step 28).

It should be noted that the above steps may be modified. For example, the values of all control parameters (i.e. position and pen-resident parameters) may be extracted in one single step. Additionally, the processing unit may, via the input interface, request transmission of further parameters from the pen. Further, step 22 may be omitted.

The flow controller may also preprocess the data received from the pens. This preprocessing may be at

Ink. t. Patent- och reg.verket

2003 -10- 3 1

Huvvunfærðin Kallast

8

In one embodiment, the flow controller is caused to render an image of the open strokes as defined by the

received data, and to transmit this stroke image to the destination unit, suitably together with a background

image that represents the graphic layout on the product on which the pen strokes were drawn by the pen. To this

end, the flow controller identifies and accesses the

relevant PAD file and graphics file, either based on the position data or as given by the processing instruction

in the storage. The processing instruction may also

identify the format in which the stroke image is to be

transmitted. Such formats include markup language (e.g.

html, xml), raster graphics (e.g. bmp, tiff, gif, png,

jpeg) and vector graphics (e.g. svg).

The above embodiment with recreation of the pen strokes has the advantage that a new product may be

created based on an existing product, by simply changing the graphical layout of the existing product. By making

the graphics file that represents the layout accessible

to the flow controller, an image of all pen strokes

recorded from such a new product can be conveyed to the

correct destination unit together with an background

image that represents the graphical layout of the new product. The PAD file may also be made accessible to the

flow controller, at least if the new product incorporates.

changes in the mapping of the logic page to the physical

product.

The above concept of forming and conveying a stroke image may also be implemented in flow controllers that

effect conventional flow control, i.e. solely based on

position data (e.g. page address). The concept gives the

general advantage of reducing or eliminating the need for

a service provider to develop software implementing the

service in the destination unit. Instead, the destination

unit may include conventional character interpretation

software (OCR/ICR) that receives and extracts relevant data from the stroke image, optionally after merging thereof with an associated background image.

5 In another embodiment, the flow controller is caused to extract data, by assigning the pen strokes to the functional areas defined in the PAD file and processing the pen strokes based on the respective functions associated with the functional areas, and then transmit such extracted data to the destination unit.

10 In all embodiments, the flow controller may also be caused to transmit the values of some or all of the extracted control parameters to the destination unit.

In these and other embodiments, the flow controller may also identify a communications channel to be used for 15 the data transfer to the destination unit, e.g. electronic mail, fax, SMS, MMS. The communications channel may be given by the processing instruction of the relevant rule object, or by a pen stroke being attributable to a dedicated area (selection box) on the product.

20 The rule object may include one or more statements that are searched sequentially. Basically, such a statement relates a control parameter to a given value. The control parameter can be any position-related or pen-resident parameter that can be sent from the pen and 25 identified by the processing unit of the flow controller. Several statements may be combined by the use of explicit or implicit logic operators (e.g. AND, OR, NAND, NOR, ANDNOT). The values may be given with arbitrary resolution, by the use of wildcards, truncations, ranges etc.

30 When all such statements of a rule object is found to be true, the associated processing instruction is executed.

Below follows an example in which an implicit logic AND operator is used. The exemplifying rule object is 35 valid for position data from a certain page address, and only for data received from pens that store pen identifiers within a specified range and pen owner electronic

1.0

mail address within a specific Internet domain. The associated processing instruction defines a destination, a format and a background image.

```
5      rule.name=demo1
      rule.page=1.231.243.333
      rule.penid=AAA-BDC-*
      rule.email=*@anoto.com
      result.destination=demo@anoto.com
10     result.format=5
      result.background=anotodemo.png
```

The use of the administrative interface 12 (Fig. 1) will now be further exemplified with reference to Fig. 3, for the case of adding a new rule object and a processing instruction to the storage. The administrative interface is designed to handle low-level accesses to the storage 10 (Fig. 1) of the flow controller. A computer is suitably connected to the interface and provided with a software module that provides access to the interface via a graphical user interface (GUI).

In the example of Fig. 3, the operator is first prompted to enter a name of the rule object to be created (step 30). Then, the software module presents the operator with a list of available pen-resident control parameters (step 31). For each selected control parameter, the operator is prompted to enter a corresponding control value according to a given format (steps 32-32'). Subsequently, the software module presents the operator with a list of available position-related control parameters (step 33). Again, the operator is prompted to enter, for each selected control parameter, a corresponding control value according to a given format (steps 34-34'). The operator is then presented with the option of selecting logic operators to combine the selected control parameters (step 35). By default, the control parameters are combined by logic AND operators. The result para-

2003-10-31

Huvudfaxen Kassan

11

5 meters are then set by the operator being prompted to enter a destination in the form of network address, e.g. a URL (Uniform Resource Locator), an IP address, an electronic mail address, a fax number, etc (step 36). If necessary, the operator is also prompted to select a communications channel. Further, the operator may also be instructed to identify the location of the PAD file for the product/logic page. The operator may also be given the option to select from a list a format of the resulting data to be conveyed to the destination unit (steps 10 37-37'), as well as an option to identify the location of a background image (steps 38-38'), whereupon the rule object is finalized and stored in the storage (step 39).

15 Again, it should be noted that the above is only an example. In another example, the software module may allow the operator to simply enter the above control statements and processing instructions.

20 Figs 4a-4c further illustrate the utility of the flow controller (denoted by reference numeral 40) in information management systems which are based on electronic pens 41 that read off position data from coded products 42 and which convey electronic data from the pens to appropriate destination units 43.

25 In Fig. 4a, the flow controller 40 is arranged as a central processing unit. Thus, the flow controller 40 communicates with the pens 41 via its input interface 4 (Fig. 1), and conveys the received electronic data, possibly after some preprocessing, via its output interface 6 (Fig. 1) to one of several destination units 43.

30 In Fig. 4b, the flow controller 40 is arranged as a router in the information management system. In this embodiment, the input and output interfaces of the flow controller may be embodied as a single I/O interface. The flow controller 40 receives data from the pens 41, and returns at least the address of the adequate destination unit to the pens. For example, the router may execute a default service of directing the pens 41 to the appro- 35

private destination unit 43 based on one or more position parameters (e.g. page address), as is known from the prior art, with the inventive flow control providing an option to break up the one-to-one relationship between product 41 and destination unit 43 in the system.

The flow control of Fig. 4b can be based on a small subset of the total data flow from the pens 41 to the destination units 43. The flow controller 40 only needs to receive the values of the relevant control parameters. In the case of preprocessing, however, the flow controller may receive at larger set, or all, of the electronic data recorded by the pens.

In Fig. 4c, the flow controller 40 is arranged as a subordinate, yet central, processing unit in the information management system. A router 44 may direct the pens 41 to the flow controller 40, e.g. based on position parameters in the recorded position data. The flow controller 40 communicates with the pens 41 via its input interface, and conveys the received electronic data, possibly after some preprocessing, via its output interface to one of several downstream destination units 43. The flow controller 40 may execute any default general or customized service, as is known from the prior art, with the inventive flow control providing an option to break up the one-to-one relationship between product 41 and destination unit 43 in the system. As mentioned above, the inventive flow control may also include preprocessing that capitalizes on any of the default service(s).

There are many variations that may be made consistent with the present invention. The foregoing description is presented for purposes of illustration and description. It is not exhaustive and does not limit the invention to the precise form disclosed. Modifications and variations are possible in light of the above teachings or may be acquired from practicing the invention.

For example, the invention is applicable in any type of electronic network, be that public or private net-

AWAPATEFT AB

+46 40 260516

→ PV *lnk. 1. Patent- och reg.verket* 015

2003-10-31

Национальный Кассет

13

works, computer or telecommunication networks, local area or wide area networks, or any combination thereof.

002 12 01 13:26 V: 07, 08, 09, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840,

+46 40 260516

Ink. t. Patent- och reg.verket

2003 -10- 3 1

Muvudfaxen Kassan

14

CLAIMS

1. An information management unit, which is arranged in an electronic network as a flow path controller for electronic data between electronic pens and destination units, the electronic data comprising handwriting data recorded by the electronic pens and one or more pen-resident parameters, said information management unit comprising:
 - means for receiving at least part of the electronic data from an electronic pen;
 - means for storing at least one flow control object and an associated processing instruction, wherein said at least one flow control object corresponds to a value of at least one of the pen-resident parameters;
 - means for mapping the thus-received electronic data against said at least one flow control object to identify a relevant processing instruction; and
 - means for directing the electronic data flow to a destination unit based on the thus-identified processing instruction.
2. The information management unit of claim 1, further comprising an administration interface which is connected to said means for storing and allows for entry of said at least one flow control object and the associated processing instruction.
3. The information management unit of claim 2, wherein the administration interface provides for election of at least one control parameter from a set of available pen-resident parameters, for setting a value of each elected control parameter, and for generating the flow control object based thereon.
4. The information management unit of claim 3, wherein the administration interface provides for election of at least two control parameters from a set of available pen-resident parameters and available parameters of the handwriting data, whereupon the values

of the thus-elected control parameters are logically combined to form the flow control object.

5. The information management unit of any preceding claim, wherein said at least one flow control object
5 comprises a set of logically combined values of control parameters present in the electronic data.

6. The information management unit of any preceding claim, wherein the associated processing instruction defines an address of one of the destination units.

10 7. The information management unit of claim 6, wherein the means for directing returns the address to the electronic pen.

8. The information management unit of claim 6, wherein the means for directing forwards the received
15 electronic data to the address.

9. The information management unit of claim 6, wherein the associated processing instruction also identifies an electronic communications service for transporting the received electronic data to the address.

20 10. The information management unit of any preceding claim, wherein the associated processing instruction identifies a format of the electronic data flow to the destination unit.

11. The information management unit of claim 10, wherein the format is based on a markup language, vector graphics, or raster graphics.

12. The information management unit of any preceding claim, wherein the associated processing instruction also identifies an image to be included in the electronic data
30 flow to the destination unit.

13. The information management unit of claim 12, wherein the image is identified as being a background image to the handwriting data.

14. The information management unit of any preceding
35 claim, which is arranged to recreate the handwriting data based on the electronic data and to forward the thus-recreated handwriting data to the destination unit.

+46 40 260516

2003 -10- 3 1

Huvudfoxen Kassan

15

15. The information management unit of any preceding claim, wherein said flow control object also corresponds to a value of at least one parameter of the handwriting data recorded by the electronic pen.

5 16. The information management unit of claim 15, wherein said at least one parameter of the handwriting data comprises a command, or an identifier related to the base on which the handwriting data was recorded by the electronic pen.

10 17. The information management unit of claim 16, wherein the identifier is at least part of an absolute position which is decoded by the electronic pen from a position code on the base during the recording of the handwriting data.

15 18. The information management unit of any preceding claim, wherein each of the pen-resident parameters identifies a characteristic of the electronic pen in the electronic network or a characteristic of the user of the electronic pen.

20 19. The information management unit of any preceding claim, wherein the pen-resident parameters comprises at least one of an identifier of the electronic pen, an identifier of the operator of the electronic network, an identifier of a geographic location, an electronic mail
25 address, a telephone number, a fax number, and an identifier of a language.

20. The information management unit of any preceding claim, wherein said value is defined as a range of values.

30 21. An information management system, comprising a plurality of electronic pens and the information management unit of any preceding claim.

22. An information management system, comprising a plurality of bases that each has a position code that
35 codes at least one absolute position, a plurality of electronic pens which record their movement on any one of said bases as handwriting data by converting the position

+46 40 260516

Ink. t. Patent- och reg.verket

2003-10-31

Huvudfaxen Kasse

17

code to said at least one absolute position, and the information management unit of claim 17.

22. A method of controlling a flow of electronic data between electronic pens and destination units in an electronic network, the electronic data comprising
5 handwriting data recorded by the electronic pens and one or more pen-resident parameters, said method comprising:

receiving at least part of the electronic data from an electronic pen;

10 mapping the thus-received electronic data against at least one flow control object to identify a relevant processing instruction, wherein said at least one flow control object corresponds to a value of one of the pen-resident parameters; and

15 directing the electronic data flow to a destination unit based on the thus-identified processing instruction.

23. The method of claim 22, further comprising providing an administration interface which allows for entry of said at least one flow control object and the
20 associated processing instruction.

24. The method of claim 23, further comprising operating the administration interface to elect of at least one control parameter from a set of available pen-resident parameters, enter a value of each elected
25 control parameter, and generate the flow control object based thereon.

25. The method of claim 24, wherein the administration interface provides for election of at least two control parameters, whereupon the values of the
30 thus-elected control parameters are logically combined to form the flow control object.

26. The method of claim 22, wherein said at least one flow control object comprises a set of logically combined control parameter values.

35

code to said at least one absolute position, and the information management unit of claim 17.

23. A method of controlling a flow of electronic data between electronic pens and destination units in an electronic network, the electronic data comprising handwriting data recorded by the electronic pens and one or more pen-resident parameters, said method comprising:

receiving at least part of the electronic data from an electronic pen;

mapping the thus-received electronic data against at least one flow control object to identify a relevant processing instruction, wherein said at least one flow control object corresponds to a value of one of the pen-resident parameters; and

directing the electronic data flow to a destination unit based on the thus-identified processing instruction.

24. The method of claim 23, further comprising providing an administration interface which allows for entry of said at least one flow control object and the associated processing instruction.

25. The method of claim 24, further comprising operating the administration interface to elect of at least one control parameter from a set of available pen-resident parameters, enter a value of each elected control parameter, and generate the flow control object based thereon.

26. The method of claim 25, wherein the administration interface provides for election of at least two control parameters, whereupon the values of the thus-elected control parameters are logically combined to form the flow control object.

27. The method of claim 23, wherein said at least one flow control object comprises a set of logically combined control parameter values.

+46 40 260516

2003 -10- 3 1

Huvudfaxen Kassen

16

ABSTRACT

An information management unit is arranged in an electronic network as a flow path controller for electronic data between electronic pens and destination units, the electronic data comprising handwriting data recorded by the electronic pens and one or more pen-resident parameters. The information management unit receives at least part of the electronic data from an electronic pen; maps the thus-received electronic data against one or more flow control objects to identify a relevant processing instruction, wherein the flow control object corresponds to a value of one of the pen-resident parameters; and directs the electronic data flow to a destination unit based on the thus-identified processing instruction.

20

25 Elected for publication: Fig 2

[illegible]

+46 40 260516

Ink. t. Patent- och reg.verket

2003-10-31

Huvudföretagen Kassen




FIG 1




FIG 4a




FIG 4b




FIG 4c

2003 -10- 3 1

Huvudföretag Kassen




FIG 2




FIG 3

**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

- ☒ **BLACK BORDERS**
- ☒ **IMAGE CUT OFF AT TOP, BOTTOM OR SIDES**
- ☒ **FADED TEXT OR DRAWING**
- ☒ **BLURRED OR ILLEGIBLE TEXT OR DRAWING**
- ☒ **SKEWED/SLANTED IMAGES**
- ☐ **COLOR OR BLACK AND WHITE PHOTOGRAPHS**
- ☐ **GRAY SCALE DOCUMENTS**
- ☒ **LINES OR MARKS ON ORIGINAL DOCUMENT**
- ☐ **REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY**
- ☐ **OTHER:** _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.